




SITE LAYOUT
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. MISCELLANEOUS

- 1.1. USE DIMENSIONS SHOWN, DO NOT SCALE DRAWING.
- 1.2. THESE PLANS ARE COPYRIGHTED BY RENEW DESIGN & CONSTRUCTION DRAWINGS. UNLAWFUL FOR USE WITHOUT PRIOR WRITTEN AUTHORIZATION.
- 1.3. THESE PLANS FORM THE BASIS FOR PERMIT ISSUANCE AND ANY DEVIATIONS FROM THESE PLANS AND DETAILS, INCLUDING THE VENTILATION SYSTEM, HEATING SYSTEM, WOOD STOVE, FIREPLACES, DECKS, BALCONIES AND FINISHED BASEMENTS, WILL REQUIRE A REVISED DRAWING AND CLEARANCE BY THE BUILDING DEPARTMENT.
- 1.4. PROVIDE TO THE BUILDING DEPARTMENT, PRIOR TO THE REQUEST FOR INSULATION INSPECTION, MECHANICAL DETAILS INCLUDING HEAT LOSS CALCULATIONS, DUCT SIZE CALCULATIONS AND DUCT LAYOUT DIAGRAM, DUCT SIZES FOR ALL VENTILATION SYSTEMS, CLASSIFICATION OF HEAT TYPE, CLASS OF VENT TYPE, LOCATION OF SUPPLEMENTAL HEATING, OR CONFIRMATION THAT NOT MORE THAN 10% OF THE HEATING WILL BE ELECTRIC AS NEEDED.
- 1.5. ALL CONSTRUCTION TO COMPLY WITH ONTARIO BUILDING CODE 2024 EDITION.
- 1.6. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONFIRMING ORDERED MATERIALS ARE TRUE AND ACCURATE PRIOR TO INSTALLATION. RENEW DESIGN & CONSTRUCTION DRAWINGS DOES NOT TAKE RESPONSIBILITY FOR ENSURING THIRD PARTY DESIGNED MATERIALS (IE: TRUSS DESIGNS, MILLWORK) CORRESPOND WITH THIS DRAWING SET.
- 1.7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION, METHOD OF ERECTION AND INSTALLATION PROCEDURES OF THE STRUCTURAL MEMBERS INCLUDING THE ERECTION OF ENGINEERED BEAMS. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION AND CARE DURING THE DEMOLITION PROCESS OF ANY EXISTING STRUCTURE.
- 1.8. THE CONTRACTOR SHALL CONFIRM BEARING PRESSURES AT THE PROPOSED BUILDING LOCATION MEET THE REQUIREMENTS OF 9.4.4.
- 1.9. ALL INTERIOR DIMENSIONS ARE TO INSIDE FACE OF STUDS (WALL THICKNESS IS NOT DIMENSIONED). EXTERIOR DIMENSIONS ARE TO OUTSIDE FACE OF OUTERMOST SHEATHING. ALL DIMENSIONS ARE IN IMPERIAL.
- 1.10. WINDOW & DOOR SIZES SHOWN ON PLANS ARE UNIT SIZES; RSO DIMENSIONS ARE PROVIDED BY THE MANUFACTURER OR SUPPLIER.

2. EXTERIOR

- 2.1. ALL CONNECTIONS OF ROOFING TO VERTICAL SURFACES TO BE FLASHED IN CONFORMANCE TO 9.26.4.4. & 9.26.4.5
- 2.2. WHERE ROOF IS CLAD WITH ASPHALT SHINGLES, EAVE PROTECTION CONFORMING TO 9.26.5.2. AT EDGES OF CONDITIONED ROOFS WITH $\leq 8/12$ SLOPE SHALL BE INSTALLED EXTENDING FROM THE ROOF EDGE A MIN. $36\frac{1}{2}$ " UP THE ROOF SLOPE TO A MIN. 12" BEYOND THE INSIDE FACE OF THE EXTERIOR WALL AS PER 9.26.5.1.
- 2.3. WHERE ROOF SOFFITS PROJECT TO LESS THAN 4'-0" FROM THE PROPERTY LINE, THEY SHALL BE PROTECTED BY UNVENTED ALUMINUM or 7/16" PLYWOOD AS PER or 1/2" OSB AS PER 9.10.14.5.(12)(b)
- 2.4. RESISTANCE TO FORCED ENTRY AS PER 9.7.3.1 & 9.7.4
- 2.5. CAULK ALL PENETRATIONS SUCH AS HOSE BIBS WITH ACOUSTIC SEALANT.
- 2.6. WHERE A WALL, CEILING OR FLOOR ASSEMBLY SEPARATES CONDITIONED FROM UNCONDITIONED SPACES, AN AIR BARRIER SYSTEM SHALL BE PROVIDED AND INSTALLED AS PER 9.25.3.

3. LOT DRAINAGE

- 3.1. FOUNDATION WALL DRAINAGE AS PER 9.14.2.
- 3.2. DRAINAGE TILE TO BE COVERED W/ MIN. $5\frac{7}{8}$ " OF CLEAR STONE
- 3.3. SUMP PIT, IF REQUIRED, TO CONFORM TO 9.14.5.2. AND SHALL BE EQUIPPED WITH A COVER DESIGNED TO RESIST THE REMOVAL BY CHILDREN
- 3.4. SUMP PIT COVERS SHALL BE SEALED TO MAINTAIN CONTINUITY OF THE AIR BARRIER SYSTEM AS PER 9.25.3.3.(10)
- 3.5. WINDOW WELLS SHALL BE DRAINED TO FOOTING LEVEL AS PER 9.14.6.3.

4. FOUNDATION/FOOTINGS

- 4.1. ALL EXTERIOR CONCRETE FLATWORK (INCLUDING STEPS, PORCH SLABS AND GARAGE SLABS) TO BE MIN 32MPa AS PER 9.3.1.6.(1)(a), 5% TO 8% AIR ENTRAINMENT AS PER 9.3.1.6.(2)
- 4.2. INTERIOR CONCRETE FLOOR SLABS TO BE MIN. 20MPa AS PER 9.3.1.6.(1)(b)
- 4.3. POURED CONCRETE WALLS & FOOTINGS TO BE MIN. 15MPa AS PER 9.3.1.6.(1)(c) UNLESS OTHERWISE SPECIFIED BY ICF MANUFACTURER (WHERE APPLICABLE)
- 4.4. FOUNDATION WALLS TO MAINTAIN MIN. 6" EXPOSURE ABOVE GRADE.
- 4.8. FOOTINGS CAN BE OMITTED UNDER WALLS THAT BEAR ON SOIL OR ROCK PROVIDED THAT THE SAFE LOADBEARING CAPACITY OF THE SOIL OR ROCK IS NOT EXCEEDED AS PER 9.15.3.1.(1). REFER TO GENERAL NOTE #1.8
- 4.9. PROVIDE 6mil POLYETHYLENE SHEET PLASTIC W/ 12" LAPPED EDGES BENEATH INTERIOR CONCRETE SLABS. EDGES & OPENINGS SEALED W/ POLYURETHANE CAULKING
- 4.10. SUBFLOOR DEPRESSURIZATION ROUGH IN TO BE INSTALLED AS PER 9.13.4.3.
- 4.11. FRAMED INSULATED WALLS AT CONDITIONED BASEMENTS TO USE A VARIABLE VAPOUR RETARDER (SMART V.B.) IN LIEU OF 6mil POLYETHYLENE.

5. STEEL BEAMS/LINTELS

- 5.1. STEEL BEAMS SHALL BE TREATED WITH MIN. 1 COAT RUST INHIBITING PAINT.
- 5.2. PROVIDE $3/4 \times 1\frac{1}{2}$ " WOOD STRIPS IN CONTACT WITH THE BEAM FLANGE (BOTH SIDES) & NAILED TO EVERY JOIST AS PER 9.23.4.3.(3)(C)
- 5.3. STEEL LINTELS TO HAVE MIN. 6" BEARING BOTH SIDES AND SHALL BE PRIMED TO PROTECT FROM CORROSION.

6. COLUMNS

- 6.1. ADJUSTABLE STEEL COLUMNS TO CONFORM TO CAN/CGSB-7.2 AS PER 9.17.3.4. AND SHALL NOT SUPPORT LOADS GREATER THAN 8000LBS.
- 6.2. COLUMNS SHALL BE SECURELY FASTENED TO THE SUPPORTED MEMBER TO REDUCE THE LIKELIHOOD OF LATERAL DIFFERENTIAL MOVEMENT AS PER 9.17.2.2.

7. STAIRS

- 7.1. MIN. RUN = 10" UNLESS NOTED OTHERWISE, MIN. TREAD = RUN + MAX. 1" NOSING
- 7.2. RISE = MAX. 7.875"
- 7.3. STRINGERS: MIN. 2x10 CONSTRUCTION SPACED MAX. 35.375" WHERE RISERS DO NOT PROVIDE SUPPORT TO THE FRONT PORTION OF THE TREAD & MAX. 47.25" WHEN SUPPORTED
- 7.4. GUARDS: MIN. 36" HIGH. CONSTRUCTION TO CONFORM TO 9.8.8.2. LOADS ON GUARDS
- 7.5. OPENINGS IN GUARDS SHALL CONFORM TO 9.8.8.5.
- 7.6. HANDRAILS: HEIGHT OF HANDRAIL MIN. 34", MAX. 38" WHERE NO GUARD IS PRESENT AS PER 9.8.7.4. INSTALLATION TO CONFORM TO 9.8.7.7.

8. FRAMING

- 8.1. ALL FRAMING LUMBER SHALL BE CONSTRUCTION GRADE APPROVED SPF #1 OR 2 KILN DRIED.
 - 8.2. NAILING FOR FRAMING TO CONFORM TO 9.23.3.4.
 - 8.3. STRUCTURAL WOOD ELEMENTS MUST BE PRESSURE TREATED TO RESIST DECAY IF LESS THAN 6" ABOVE THE GROUND. IN AREA WHERE TERMITES ARE KNOWN TO OCCUR, CLEARANCE BETWEEN STRUCTURAL WOOD ELEMENTS AND THE GROUND MUST BE AT LEAST 18" UNLESS TREATED AGAINST TERMITES.
 - 8.4. WOOD FRAMING, INCLUDING COLUMNS AND WALLS TO BE SEPARATED FROM CONCRETE BY 0.05MM POLYETHYLENE FILM OR TYPE S ROLL ROOFING AS PER 9.17.4.3.(1) & 9.23.2.3.(1)
 - 8.5. WHERE BRIDGING AND/OR STRAPPING IN FLOOR JOISTS IS SPECIFIED, IT SHALL BE LOCATED NO MORE THAN 6'-10 1/2" FROM EACH SUPPORT OR OTHER ROW OF BRIDGING/STRAPPING & FASTENED AT EACH END TO A SILL OR HEADER.
 - 8.6. STRAPPING CAN BE OMITTED WHERE A PANEL TYPE CEILING FINISH COMPLYING WITH 9.29.5., 9.29.6., 9.29.7., 9.29.8., OR 9.29.9. IS ATTACHED DIRECTLY TO THE JOISTS.
 - 8.7. HOLES DRILLED IN FLOOR JOISTS TO BE MAX. 1/4 DEPTH OF JOIST IN DIAMETER & MIN. 2" FROM ANY JOIST EDGE
 - 8.8. TONGUE & GROOVE SUBFLOOR TO BE GLUED & SCREWED TO JOISTS, TYPICAL
 - 8.9. STUD HEIGHTS TO CONFORM TO 9.23.10.1
 - 8.10. LOAD BEARING & EXTERIOR STUD WALLS SHALL BE CONSTRUCTED FREE OF HINGE POINTS AS PER 9.23.10.4.. STUDS SHALL BE CONTINUOUS FROM BOTTOM PLATE TO TOP PLATES WITH NO BREAKS EXCEPT AT RSOs
 - 8.11. PROVIDE SOLID HORIZONTAL BLOCKING AT MAX. 3'-11" O.C. VERTICALLY IN LOAD BEARING WALLS EXCEEDING 9'-10" IN HEIGHT.
 - 8.12. INTERIOR LOAD BEARING WALLS NOT SHEATHED WITH PANELING OR GYPSUM IN ACCORDANCE WITH 9.29. SHALL HAVE SOLID HORIZONTAL BLOCKING AT MID-HEIGHT TO PREVENT SIDEWAYS BUCKLING.
 - 8.13. ALL BLOCKING AT WATER CLOSET, BATHTUB AND/OR SHOWER AT MAIN BATHROOM TO CONFORM TO 9.5.2.4.
 - 8.14. ALL INTERIOR PARTITIONS TO BE 2x4@24" O.C. UNLESS NOTED OTHERWISE WITH 1 LAYER 1/2" GYPSUM WALLBOARD BOTH SIDES.
 - 8.15. ALL PARTITIONS RUNNING PARALLEL TO FLOOR JOISTS SHALL BE SUPPORTED BY 2x4 BLOCKING SPACED NOT MORE THAN 3'-11" AS PER 9.23.9.8.
 - 8.16. WALL, ROOF AND FLOOR ASSEMBLIES AS PER ASSEMBLY NOTES.
 - 8.17. PROVIDE HURRICANE TIES AT ALL RAFTER/ROOF JOIST TO WALL CONNECTIONS, WHERE APPLICABLE, AND TRUSS TO WALL CONNECTIONS IF NOT SPECIFIED BY TRUSS MANUFACTURER.
 - 8.18. INTERIOR AND EXTERIOR GUARDS INCLUDING $\frac{1}{2}$ WALLS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH SB-7.
 - 8.19. WOOD ROOF TRUSSES INSTALLATION, BRACING, DESIGN AS PER 9.23.14.11.
 - 8.20. WHERE STUD POSTS ARE PRESENT, THE WIDTH OF THE STUD POST SHALL BE NOT LESS THAN THE WIDTH OF THE GIRDER OR BEAM THAT IT SUPPORTS, AS PER 9.23.10.7.(3)
 - 8.21. PROVIDE SOLID BLOCKING IN JOIST CAVITIES BELOW POINT LOADS
 - 8.22. BEAMS SHALL HAVE MIN. $3\frac{1}{2}$ " BEARING AS PER 9.23.8.1.
 - 8.23. 6x6 WOOD POST TO BUILT UP WOOD BEAM CONNECTIONS TO INCLUDE LPC6Z AT POST TOP & BC60Z AT POST BASE. FASTENERS AS PER MANUFACTURER'S SPECIFICATIONS.
 - 8.24. WHERE 5/4"x6" PRESSURE TREATED DECKING IS SUBSTITUTED WITH COMPOSITE DECKING, DECK JOIST SPACING TO BE REDUCED TO MAX. 12" O.C. UNLESS OTHERWISE SPECIFIED BY THE COMPOSITE DECKING MANUFACTURER.
 - 8.25. CUT ENDS OF PRESSURE TREATED LUMBER TO BE RE-TREATED WITH SEALER.
 - 8.26. EXTERIOR HANGERS & POST BRACKETS TO HAVE SIMPSON STRONG-TIE ZMAX FINISH OR EQUIVALENT
9. ELECTRICAL
- 9.1. WHERE ELECTRICAL SERVICES ARE AVAILABLE, LOCATIONS OF LIGHT FIXTURES, SWITCHES AND OUTLETS SHALL MEET SECTION 9.34.1 THRU 9.34.3., INCLUDING BUT NOT LIMITED TO, PROVIDING AN OUTLET WITH FIXTURE CONTROLLED BY A WALL SWITCHED IN EVERY KITCHEN, BEDROOMS, LIVING ROOMS, UTILITY ROOM, LAUNDRY ROOM, DINING ROOMS, BATHROOMS, WATER-CLOSET ROOMS, VESTIBULES, HALLWAYS, STORAGE ROOMS, AND GARAGES
 - 9.2. WHERE A RECEPTABLE CONTROLLED BY A WALL SWITCH IS PROVIDED IN BEDROOMS OR LIVING ROOMS, SUCH ROOMS NEED NOT PROVIDE A LIGHTING FIXTURE
 - 9.3. A LIGHTING OUTLET WITH FIXTURE CONTROLLED BY A WALL SWITCH SHALL BE PROVIDED FOR EACH 322.9sqft IN UNFINISHED BASEMENTS AND THE OUTLET NEAREST THE STAIRS SHALL BE CONTROLLED BY A WALL SWITCH AT THE HEAD OF THE STAIRS.
 - 9.4. PROVIDE 3-WAY SWITCHES AT HEAD & FOOT OF EVERY INTERIOR STAIRWAY, OF 4 OR MORE RISERS, CONTROLLING AT LEAST ONE LIGHTING FIXTURE SERVING THE STAIR AS PER 9.34.2.3.
 - 9.5. EVERY EXTERIOR DOOR FROM THE DWELLING SHALL BE EQUIPPED WITH A LIGHT FIXTURE OPERATED BY A SWITCH INSIDE THE DWELLING AS PER 9.34.2.1.
 - 9.6. SMOKE ALARM CONFORMANCE AND LOCATION AS PER 9.10.19. AND SHALL BE INTERCONNECTED AS PER 9.10.19.5.
 - 9.7. CARBON MONOXIDE ALARMS TO BE INSTALLED AND LOCATED AS PER 9.32.3.9A., INCLUDING ON EACH STOREY, ADJACENT TO SLEEPING AREAS AND IN SLEEPING ROOMS THAT SHARE A COMMON WALL OR FLOOR ASSEMBLY WITH A ROOM OR SPACE CONTAINING A FUEL-BURNING APPLIANCE OR AN ATTACHED GARAGE AS PER 6.9.3.2.(4)
 - 9.8. ALL OUTLETS TO BE GFI PROTECTED WHEN WITHIN 1M OF A SOURCE OF WATER, INCLUDING EXTERIOR, EXCLUDING LAUNDRY TUBS.
10. PLUMBING
- 10.1. ALL TOILETS TO CONFORM TO 7.6.1.6. & 7.6.2.11.
 - 10.2. ALL SHOWER VALVES TO BE PRESSURE BALANCED OR THERMOSTATICALLY CONTROLLED AS PER 7.2.10.7B.
 - 10.3. HOT WATER SUPPLY FROM HOT WATER TANK TO BE EQUIPPED WITH MIXING VALVE TO TEMPER WATER TO MAXIMUM 49°C TEMPERATURE AS PER 7.2.10.7.
 - 10.4. BACKWATER VALVE TO BE INSTALLED AS PER 7.2.10.10.
 - 10.5. ALL FLOOR DRAINS TO CONFORM TO 7.5.1.1. AND BE EQUIPPED WITH A TRAP SEAL PRIMER IN CONFORMANCE WITH 7.4.5.5.
 - 10.6. DRAIN WATER HEAT RECOVERY INSTALLED AS PER SB-12 3.1.1.12. WHERE STOREY OR CRAWLSPACE IS LOCATED BELOW ANY OF THE SHOWERS PROVIDED.
11. ATTACHED GARAGE
- 11.1. ALL DOORS BETWEEN AN ATTACHED OR BUILT-IN GARAGE AND A DWELLING UNIT SHALL HAVE A SELF CLOSING DEVICE & BE TIGHT FITTING AND WEATHERSTRIPPED TO PROVIDE AN EFFECTIVE BARRIER AGAINST THE PASSAGE OF EXHAUST & GAS FUMES AS PER 9.10.13.15
 - 11.2. SEPARATION OF GARAGE TO DWELLING TO CONFORM TO 9.10.9.18.(4)
 - 11.3. WHERE ATTACHED GARAGE IS ADJACENT TO ATTIC SPACE CARRY GYPSUM BOARD VERTICALLY TO ROOF SHEATHING AND CAULK WITH ACOUSTIC SEALANT, OR INCLUDE 1/2" GYPSUM TO ENTIRE GARAGE CEILING, TAPED, MUDDED & CAULKED TO PROVIDE SEAL.

Notes:

Details including engineered trusses, ICF & rebar and in-floor heating should be designed by qualified professionals.

Plans are for permit issuance. Alterations to the plan will require revised drawings and building department approval.

Plans are not to be scaled. Contractor to verify all existing conditions and dimensions required to perform the work.

Andrew Snelling
Andrew Snelling BCIN: 111876 has reviewed and takes responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Divisions C of the 2024 Ontario Building Code. Firm BCIN: 129800

PROJECT:

**30 Exeter Court
Quinte West, ON**

New single family bungalow w/
attached garage & 13'-6"x12'-6"
rear porch



Main Floor: 1,670sqft
Finished Basement: ---sqft
Print to 18x24 paper size

DRAWN: Andrew Snelling
SCALE: As Noted
DATE: August 13, 2026

renew
DESIGN &
CONSTRUCTION
DRAWINGS

7532 7th Concession Rd,
Addison ON K0E 1A0
613.893.0493
andrew@renewplans.com

A1.1



ELEVATIONS
SCALE: 3/16" = 1'-0"

Notes:
Details including engineered trusses, ICF & rebar and in-floor heating should be designed by qualified professionals.

Plans are for permit issuance. Alterations to the plan will require revised drawings and building department approval.

Plans are not to be scaled. Contractor to verify all existing conditions and dimensions required to perform the work.

Andrew Snelling
Andrew Snelling BCIN: 111876 has reviewed and takes responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Divisions C of the 2024 Ontario Building Code. Firm BCIN: 129800

PROJECT:
**30 Exeter Court
Quinte West, ON**

New single family bungalow w/
attached garage & 13'-6"x12'-6"
rear porch



Main Floor: 1,670sqft
Finished Basement: ---sqft
Print to 18x24 paper size

DRAWN: Andrew Snelling
SCALE: As Noted
DATE: August 13, 2026

renew
DESIGN &
CONSTRUCTION
DRAWINGS

7532 7th Concession Rd,
Addison ON K0E 1A0
613.893.0493
andrew@renewplans.com

A1.2



ELEVATIONS
SCALE: 3/16" = 1'-0"

Notes:
Details including engineered trusses, ICF & rebar and in-floor heating should be designed by qualified professionals.

Plans are for permit issuance. Alterations to the plan will require revised drawings and building department approval.

Plans are not to be scaled. Contractor to verify all existing conditions and dimensions required to perform the work.

Andrew Snelling
Andrew Snelling BCIN: 111876 has reviewed and takes responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Divisions C of the 2024 Ontario Building Code. Firm BCIN: 129800

PROJECT:
**30 Exeter Court
Quinte West, ON**

New single family bungalow w/
attached garage & 13'-6"x12'-6"
rear porch


Main Floor: 1,670sqft
Finished Basement: ---sqft
Print to 18x24 paper size

DRAWN: Andrew Snelling
SCALE: As Noted
DATE: August 13, 2026


renew
DESIGN &
CONSTRUCTION
DRAWINGS

7532 7th Concession Rd,
Addison ON K0E 1A0
613.893.0493
andrew@renewplans.com

A1.3



FOUNDATION
SCALE: 3/16" = 1'-0"



MAIN FLOOR
SCALE: 3/16" = 1'-0"

Notes:
Details including engineered trusses, ICF & rebar and in-floor heating should be designed by qualified professionals.

Plans are for permit issuance. Alterations to the plan will require revised drawings and building department approval.

Plans are not to be scaled. Contractor to verify all existing conditions and dimensions required to perform the work.

Andrew Snelling
Andrew Snelling BCIN: 111876 has reviewed and takes responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Divisions C of the 2024 Ontario Building Code. Firm BCIN: 129800

PROJECT:
**30 Exeter Court
Quinte West, ON**

New single family bungalow w/
attached garage & 13'-6"x12'-6"
rear porch










Main Floor: 1,670sqft
Finished Basement: ---sqft
Print to 18x24 paper size

DRAWN: Andrew Snelling
SCALE: As Noted
DATE: August 13, 2026

renew
DESIGN &
CONSTRUCTION
DRAWINGS

7532 7th Concession Rd,
Addison ON K0E 1A0
613.893.0493
andrew@renewplans.com

A1.4



Notes:
Details including engineered trusses, ICF & rebar and in-floor heating should be designed by qualified professionals.

Plans are for permit issuance. Alterations to the plan will require revised drawings and building department approval.

Plans are not to be scaled. Contractor to verify all existing conditions and dimensions required to perform the work.

Andrew Snelling
Andrew Snelling BCIN: 111876 has reviewed and takes responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Divisions C of the 2024 Ontario Building Code. Firm BCIN: 129800

PROJECT:
30 Exeter Court
Quinte West, ON

New single family bungalow w/
attached garage & 13'-6"x12'-6"
rear porch

Main Floor: 1,670sqft
Finished Basement: ---sqft
Print to 18x24 paper size

DRAWN: Andrew Snelling
SCALE: As Noted
DATE: August 13, 2026

renew
DESIGN &
CONSTRUCTION
DRAWINGS

7532 7th Concession Rd,
Addison ON K0E 1A0
613.893.0493
andrew@renewplans.com

A1.5